

1 / M1-1 MECHANICAL COOPER COMMONS - LEVEL 1
1/4" = 1'-0"

MECHANICAL DUCTWORK LEGEND

- NEW CONSTRUCTION DUCTWORK
- EXISTING DUCTWORK
- DEMOLISHED DUCTWORK

MECHANICAL - KEYNOTE LEGEND	
Key Value	Keynote Text
1M	EXISTING INDOOR VRF FAN COIL TO BE REMOVED. UTILIZE THE EXISTING DUCTWORK AS SHOWN WITH RTU-1.
13M	CONNECT TO EXISTING DUCTWORK.
22M	CAP DUCT OPENING CREATED DURING DEMO.
23M	SUPPLY DROP FROM ROOF MOUNTED RTU-1.
29M	RETURN DIFFUSER MOUTED TO SECOND LEVEL CEILING SEE SHEET M1-3 FOR ADDITIONAL DETAILS.

GENERAL NOTES:
1. ALL EXISTING MECHANICAL SYSTEMS TO REMAIN, EXCEPT AS NOTED.
2. ALL EXPOSED DUCTWORK TO BE PAINTABLE TYPE AND TO BE PAINTED PER ARCHITECT'S REQUIREMENTS.

Colorado Mountain College

PROJECT DESCRIPTION

Delta	Description	Date Issued
1	ADDENDUM #002	9/8/16

HUMPHRIES POLI ARCHITECTS

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by the Architect as instruments of service shall remain the property of the Architect. The Architect shall retain all common law, statutory and other reserved rights, including copyright thereto.

MECHANICAL PLAN - COOPER COMMON

BIDDING/PERMIT SET
8/01/2016

PROJECT No.	PROJECT ARCH	PROJECT MNGR	CHECKED BY
16-001	Approver	Designer	Checker

SHEET No.

M1-1

9/9/2016 9:58:41 AM